



Technical Report No.: 64.181.23.03037.01 Rev.00

Date: 2023-11-07

Client: Name: Guangzhou Sprsun New Energy Technology Development

Co., Ltd

Address: No.15 Tangxi Road, Yinsha Industrial Park, Xintang,

Zengcheng District, Guangzhou, 511338, China

Contact person: YE XIN

Manufacturer: Name: Guangzhou Sprsun New Energy Technology Development

Co., Ltd

Address: No.15 Tangxi Road, Yinsha Industrial Park, Xintang,

Zengcheng District, Guangzhou, 511338, China

Factory: Name: Guangzhou Sprsun New Energy Technology Development

Co., Ltd

Address: No.15 Tangxi Road, Yinsha Industrial Park, Xintang,

Zengcheng District, Guangzhou, 511338, China

Test object: Product: DC Inverter Air Source Heat Pumps

Model: CGK-030V4P, CGK-040V4P, CGK-050V4P, CGK-060V4P

Trade mark: SPRSUN

Test specification: ☑ EN 14825:2022

☑ EN 12102-1:2022

☑ EN 14511-3:2022

☑ EN 14511-4:2022 Clause 4

Purpose of Test according to the test specification

examination:

☑ (EU) No 813/2013

EU 2016/2282:2016-11-30

Test result: The test results show that the presented product is in compliance with the above

listed test specifications.

Any use for advertising purposes must be granted in writing. This technical report may only be quoted in full. This report is the result of a single examination of the object in question. It does not imply a general statement regarding the quality of products from regular production. For further details please see testing and certification regulation, chapter A-3.4.

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-

Date: 2023-11-07 Page: 1 of 59 www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





#### Description of the test object 1

#### 1.1 **Function**

1.3

Manufacturer's specification for intended use:

The appliance is air to water heat pump.

Manufacturer's specification for predictive use:

According to user manual

1.2 Consideration of the foreseeable us
---

Covered through the applied	standard
☐ Covered by the following com	ment
☐ Covered by attached risk ana	lysis
Technical Data	
Model:	CGK-030V4P, CGK-040V4P, CGK-050V4P, CGK-060V4F
Rated Voltage (V):	380-420V , 3N~
Rated Frequency (Hz):	50
Rated Power (W):	4310 for CGK-030V4P; 5050 for CGK-040V4P; 6800 for CGK-050V4P; 7830 for CGK-060V4P
Rated Current (A):	9.09 for CGK-030V4P; 10.66 for CGK-040V4P; 14.35 for CGK-050V4P; 16.53 for CGK-060V4P
Protection Class :	Class I
Protection Against Moisture:	IP X4
Construction:	Stationary
Supply connection :	☐ Non detachable cord
	<ul> <li>Permanent connection to fixed wiring</li> </ul>
Operation mode:	<ul><li>Continuous operation;</li></ul>
	☐ Intermittent operation;
	☐ Short time operation;
Refrigerant/charge (kg):	R290 / 0.80 for CGK-030V4P; 1.00 for CGK-040V4P; 1.20 for CGK-050V4P; 1.80 for CGK-060V4P
Declared parameters :	☑ Average ☐ Warmer ☐ Colder
Sound power level dB(A):	N/A
Series No:	KAL092210600600093 for CGK-030V4P; KAL092210600700014 for CGK-040V4P; KAL092210600800135 for CGK-050V4P;

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 2 of 59

www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



KAL092210600900026 for CGK-060V4P



#### 2 Order

#### 2.1 Date of Purchase Order, Customer's Reference

Date of Purchase Order: 2023-08-03

Customer's Reference: Guangzhou Sprsun New Energy Technology Development Co., Ltd

#### 2.2 Test Sample(s)

• Reception date(s): 2023-08-07

· Location(s) of reception:

For Energy test:

Guangzhou Customs District Technology Center

(CNAS accredited laboratory with Registration No.CNAS L2322)

Address: No.3, Desheng East Road, Daliang, Shunde District, Foshan, Guangdong, China

For Noise tests:

CVC Testing Technology Co., Ltd.

(CNAS accredited laboratory with Registration No.CNAS L0095)

Address: No.3, Tiantai Yilu, Kaitai Avenue, Science City, Guangzhou, Guangdong, China

• Condition of test sample(s): completed and can be normal operation

#### 2.3 Date(s) of Testing

2023-08-07 to 2023-10-30

#### 2.4 Location(s) of Testing

Same as 2.2

#### 2.5 Points of Non-compliance or Exceptions of the Test Procedure

N/A

#### 3 Test Results

1 Cot No outo
☑ Decision rule according to ILAC-G8:09/2019 clause 4.2.1 Binary statement for simple acceptance rule or IEC Guide 115:2023, clause 4.3 Simple acceptance was applied.
<ul> <li>□ Decision rule according to customer's requirements was applied. It is:</li> <li>□ Decision rule according to ILAC-G8:09/2019 clause 4.2.2 Binary statement with guard band - guard band length = 95 % extended measurement uncertainty, was applied.</li> </ul>
□ Decision rule (based on ILAC-G8:09/2019 clause 4.2.3 Non-binary statement with guard band, guard band length = 95 % extended measurement uncertainty) for an upper specification limit (A lower limit or specification with an up-per and a lower limit is treated similarly.):
•Compliance with the requirement: If a specification limit is not breached by a measurement
result plus the expanded uncertainty with a 95% coverage probability, then compliance with the
specification will be stated (e. g. Pass).
• Non-compliance with the requirement: If a specification limit is exceeded by the measurement
result minus the expanded uncertainty with a 95% coverage probability, then non-compliance with the specification will be stated (e. g. Fail).
· I $\Box$ nconclusive result: If a measurement result plus/minus the expanded uncertainty with a 95 $\%$

•1⊔ nconclusive result: If a measurement result plus/minus the expanded uncertainty with a 95 % coverage probability overlaps the limit it will be stated that it is not possible to state compliance or non-compliance.

☐ There are no statements to conformity or no results with measurand stated in this report, no decision rule has been applied.

www.tuvsud.com

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 3 of 59

TI"N®

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



#### 3.1 Positive Test Results

See Appendix I

#### 4 Remarks

#### 4.1 General

The user manual has been examined according to the minimum requirements described in the product standard. The manufacturer is responsible for the accuracy of further par-ticulars as well as of the composition and layout.

**4.2** When the product is placed on the market, it must be accompanied with safety Instructions written in official language of the country. The instructions shall give information re-garding safe operation, installation and maintenance.

#### 5 Documentation

· Appendix I: Test results

Appendix II: Marking plate

· Appendix III: photo documentation

· Appendix IV: Construction data form

• Appendix V: Test equipment list

#### 6 Test History

- 1) These appliances are Air To Water Heat Pump Unit, each one including a whole compression type refrigerant circuit to heat water in another circuit. These appliances were for cooling and heating water function, this report only for heating capacity test.
- 2) The main power is supplied by a 5-pole supply cord connecting to fixed wiring.
- 3) Water enthalpy method was adopted in this report.
- 4) Standby mode power, off mode power and thermostat-off mode power were tested according to clause 12 of standard EN 14825:2022.

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch
TÜV SÜD Group

Tested by: William Liang, Project Handler

printed name, function & signature

Approved by: Plum Li, Designated Reviewer

printed name, function & signature

www.tuvsud.com

Rev.: 00 Date: 2023-11-07 Page: 4 of 59

Project No: 64.181.23.03037.01

TÜV®

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 1.	Heating mode (Low temperature application):							Р	
Model	CGK-030V4P								
Product type	Air to Water	Heating season	7	Average		Warmer		Colder	
1. Test condit	ions:		•		•	•	•		
O a malistica m	I	Part Load Ra	atio		hea	Outdoor heat exchanger			or heat anger
Condition	Form	nula		verage imates		t dry (wet) k nperature (			tlet water tures (°C)
А	(-7-16)/(Tde	esignh-16)		88		-7(-8)		а	/ 34
В	(+2-16)/ (To	designh-16)		54		2(1)		а	/ 30
С	(+7-16)/(Tde	esignh-16)		35		7(6)		а	/ 27
D	(+12-16)/(To	lesignh-16)		15		12(11)		а	/ 24
E	(TOI	16)/ (Tdesi	gnh-16	5)		TOL		a/	35.3
F	(Tbival	ent-16)/(Tdes	ignh-1	6)		Tbiv		a / 34	
G	(-15-16)/(Td	esignh-16)		N/A		-15		N	I/A
conditions, the conditions at the conditions.	/correction	data(Averag	je):						
General test conditions/ Part-Load	Unit	A(-7)/W34 (88%)		2/W30 (54%)	A7/W2 (35%		2/W24 5%)	A(-10)/ W35.3 (100%)	A(-7)/W34 (88%)
		А		В	С		D	Е	F
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	00 1:	10:00	3:00:00	3:00:00
The heat pump defrosts		Yes		No	No		No	Yes	Yes
Electrical Prop	erties								
Voltage	V	400.3		400.9	400.9	9 4	00.9	400.3	400.3
Current input of the unit	А	3.85		1.64	1.49	1	.32	3.86	3.85
Power input of the unit	kW	2.054	(	0.793	0.705	5 0	.607	2.064	2.054
Compressor frequency	Hz	70		30	30		30	70	70

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 5 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Test conditions User Side									
Water flow	m³/h	1.31	1.31	1.31	1.31	1.31	1.31		
Inlet Water temperature	°C	29.78	27.52	25.50	23.34	31.34	29.78		
Outlet Water temperature	°C	33.67*	30.05	28.41	26.63	34.97*	33.67*		
Test conditions Source Side									
Barometric pressure	kPa	101.02	101.01	101.01	101.02	101.01	101.02		
Air <b>inlet</b> temperature, DB	°C	-7.00	2.00	7.00	12.00	-10.00	-7.00		
Air <b>inlet</b> temperature, WB	°C	-7.99	1.00	6.00	11.00	-11.00	-7.99		
Summary of th	e results								
Total heating capacity	kW	5.871	3.814	4.394	5.020	5.461	5.871		
Effective power input	kW	2.024	0.763	0.675	0.577	2.034	2.024		
Coefficient of performance (COP)	kW/kW	2.90	5.00	6.51	8.70	2.69	2.90		

Remark: \* In part condition, outlet temperature data is recorded by the full average complete cycle's data.

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.035
Standby mode [P <sub>SB</sub> ]	kW	0.024
Crankcase heater [P <sub>CK</sub> ]	kW	0.042
Off mode [P <sub>OFF</sub> ]	kW	0.024

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 6 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





3.Calculation/conclusion for SCOP:									
Tdesignh(°C):	-10		Tbiv(°C):	-7					
Pdesignh(kW):	6.636		TOL(°C):	-10					
Test result A, B, C, D, E, F conditions:									
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load			
E	6.636	5.461	2.69	0.90	1.00	2.69			
F	5.871	5.871	2.90	0.90	1.00	2.90			
Α	5.871	5.871	2.90	0.90	1.00	2.90			
В	3.573	3.814	5.00	0.90	0.94	5.00			
С	2.297	4.394	6.51	0.90	0.52	5.96			
D	1.021	5.020	8.70	0.90	0.20	6.25			
CR: part load divided by capacity;									

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.79
SCOP:	kWh/kWh	4.77
Q <sub>H</sub> :	kWh/year	13710
Q <sub>HE</sub> :	kWh/year	2874
$\eta_{s,h}$	%	187.8
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 7 of 59

www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Table 2.	Heating mode (Medium temperature application):							Р	
Model	CGK-030V4P								
Product type	Air to Water	Heating season	7	Average		Warmer		Colder	
1. Test condit	ions:							•	
	F	Part Load Ra	atio			Outdoor			or heat
Condition	Form	in %	Ι Δ.			at exchang		+	anger
	Folii	iuia		verage imates		t dry (wet) b nperature (			tlet water tures (°C)
А	(-7-16)/(Tde	signh-16)		88		-7(-8)		а	/ 52
В	(+2-16)/ (Td	lesignh-16)		54		2(1)		a.	/ 42
С	(+7-16)/(Tde	esignh-16)		35		7(6)		а	/ 36
D	(+12-16)/(Td	esignh-16)		15		12(11)		a,	/ 30
E	(TOL	16)/ (Tdesi	gnh-16	5)		TOL		a/	55.3
F	(Tbival	ent-16)/(Tdes	signh-1	16)		Tbiv		a / 52	
G	(-15-16)/(Tde		N/A		-15		N	I/A	
conditions, the conditions and conditions are conditions.				3 2.236kW,	the COF	' is 3.05kW	/kW.		
General test conditions/ Part-Load	Unit	A(-7)W52 (88%)		2/W42 (54%)	A7/W3 (35%		2/W30 5%)	A(-10)/ W55.3 (100%)	A(-7)/W52 (88%)
		Α		В	С		D	Е	F
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	00 1:1	10:00	3:00:00	3:00:00
The heat pump defrosts		Yes		No	No		No	Yes	Yes
Electrical Prop	erties							•	
Voltage	V	400.1		400.8	400.9	9 4	00.9	400.1	400.1
Current input of the unit	А	4.53		1.92	1.80	1	.61	4.52	4.53
Power input of the unit	kW	2.444	(	0.943	0.869	9 0	.759	2.439	2.444
Compressor frequency	Hz	70		30	30		30	70	70


Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 8 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Test conditions User Side										
Water flow	m³/h	0.75	0.75	0.75	0.75	0.75	0.75			
Inlet Water temperature	°C	45.03	37.90	33.42	28.87	48.94	45.03			
Outlet Water temperature	°C	51.56*	41.97	38.21	34.41	54.75*	51.56*			
Test condition	Test conditions Source Side									
Barometric pressure	kPa	99.85	99.85	99.85	99.80	99.75	99.85			
Air <b>inlet</b> temperature, DB	°C	-6.99	2.00	7.01	12.01	-10.00	-6.99			
Air <b>inlet</b> temperature, WB	°C	-7.99	1.00	6.01	11.00	-10.93	-7.99			
Summary of th	e results									
Total heating capacity	kW	5.617	3.520	4.147	4.800	4.996	5.617			
Effective power input	kW	2.441	0.940	0.866	0.756	2.436	2.441			
Coefficient of performance (COP)	kW/kW	2.30	3.75	4.79	6.35	2.05	2.30			

Remark: \* In part condition, outlet temperature data is recorded by the full average complete cycle's data.

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.035
Standby mode [P <sub>SB</sub> ]	kW	0.024
Crankcase heater [P <sub>CK</sub> ]	kW	0.042
Off mode [P <sub>OFF</sub> ]	kW	0.024

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 9 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





3.Calculation/conclusion for SCOP:									
Tdesignh(°C):	-10		Tbiv(°C):	-7					
Pdesignh(kW):	6.349		TOL(°C):	-10					
Test result A, B, C, D, E, F conditions:									
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load			
E	6.349	4.996	2.05	0.90	1.00	2.05			
F	5.617	5.617	2.30	0.90	1.00	2.30			
А	5.617	5.617	2.30	0.90	1.00	2.30			
В	3.419	3.520	3.75	0.90	0.97	3.75			
С	2.198	4.147	4.79	0.90	0.53	4.40			
D	0.977	4.800	6.35	0.90	0.20	4.56			
CR: part load di	vided by capac	ity;							

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.61
SCOP:	kWh/kWh	3.60
Q <sub>H</sub> :	kWh/year	13118
Q <sub>HE</sub> :	kWh/year	3642
$\eta_{s,h}$	%	141.1
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 10 of 59 www.tuvsud.com

TÜV®



Table 3.	Heating mode (Low temperature application):							Р	
Model	CGK-040V4P								
Product type	Air to Water	Heating season	7	Average		Warmer		Colder	
1. Test condit	ions:	·						•	
	ı	Part Load Ra	atio			Outdoor			or heat
Condition	Form	in %	Ι	vorage		at exchang		1	anger
	Folli	iuia		verage imates		t dry (wet) l nperature (			tlet water tures (°C)
А	(-7-16)/(Tde	esignh-16)		88		-7(-8)		a /	/ 34
В	(+2-16)/ (To	lesignh-16)		54		2(1)		a,	/ 30
С	(+7-16)/(Tdesignh-16)			35		7(6)		a,	/ 27
D	(+12-16)/(Td	esignh-16)		15		12(11)		a,	/ 24
E	(TOL	-16)/ (Tdesi	gnh-16	5)		TOL		a / 35.3	
F	(Tbival	ent-16)/(Tdes	signh-1	16)	Tbiv a/3		/ 34		
G	(-15-16)/(Td	)/(Tdesignh-16)				I/A			
conditions, the conditions at the conditions.				, 1.707KVV,		13 4.0180	V/ICVV.		
General test conditions/ Part-Load	Unit	A(-7)W34 (88%)		2/W30 (54%)	A7W2 (35%		2/W24 15%)	A(-10)/ W35.3 (100%)	A(-7)W34 (88%)
		А		В	С		D	Е	F
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	00 1:	10:00	3:00:00	3:00:00
The heat pump defrosts		Yes		No	No		No	Yes	Yes
Electrical Prop	erties								
Voltage	V	400.3		401.0	401.1	1 4	01.1	400.3	400.3
Current input of the unit	А	4.29		1.85	1.50		1.40	4.55	4.29
Power input of the unit	kW	2.298	(	0.898	0.694	4 0	.622	2.454	2.298
Compressor frequency	Hz	78		35	30		30	83	78

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 11 of 59

**®** 

www.tuvsud.com Guangz

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Test conditions	s User Side						
Water flow	m³/h	1.40	1.40	1.40	1.40	1.40	1.40
Inlet Water temperature	°C	29.32	27.23	25.33	23.27	30.93	29.32
Outlet Water temperature	°C	33.55*	29.94	28.06	26.41	35.02*	33.55*
Test conditions	s Source Side						
Barometric pressure	kPa	101.02	101.01	101.01	101.02	101.01	101.02
Air <b>inlet</b> temperature, DB	°C	-6.98	2.01	7.00	12.00	-9.99	-6.98
Air <b>inlet</b> temperature, WB	°C	-7.93	1.03	6.01	10.99	-11.03	-7.93
Summary of th	e results						
Total heating capacity	kW	6.845	4.394	4.423	5.085	6.613	6.845
Effective power input	kW	2.293	0.892	0.689	0.617	2.449	2.293
Coefficient of performance (COP)	kW/kW	2.99	4.92	6.42	8.24	2.70	2.99

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.030
Standby mode [P <sub>SB</sub> ]	kW	0.024
Crankcase heater [P <sub>CK</sub> ]	kW	0.043
Off mode [P <sub>OFF</sub> ]	kW	0.024

Project No: 64.181.23.03037.01

Date: 2023-11-07 Page: 12 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

Tel: +86 20 38320668

Doc No.: ITC-TTW0902.02E - Rev.13



3.Calculation/	conclusion f	or SCOP:							
Tdesignh(°C):	-10		Tbiv(°C):	-7					
Pdesignh(kW):	7.738		TOL(°C):	-10	-10				
Test result A,	B, C, D, E, F	conditions	s:						
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load			
E	7.738	6.613	2.70	0.90	1.00	2.70			
F	6.845	6.845	2.99	0.90	1.00	2.99			
А	6.845	6.845	2.99	0.90	1.00	2.99			
В	4.167	4.394	4.92	0.90	0.95	4.92			
С	2.678	4.423	6.42	0.90	0.61	6.03			
D	1.190	5.085	8.24	0.90	0.23	6.21			
CR: part load di	vided by capac	ity;		•	1				

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.80
SCOP:	kWh/kWh	4.78
Q <sub>H</sub> :	kWh/year	15986
Q <sub>HE</sub> :	kWh/year	3345
$\eta_{s,h}$	%	188.2
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 13 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China






Table 4.	Heating mode (Medium temperature application):							P		
Model	CGK-040V4P							1		
Product type Air to Water		Heating season	V	Average		Warmer		Colder		
1. Test condit	ions:	•					1	1		
	ı	Part Load Ra	atio			Outdoor		Indoo	or heat	
Condition		in %			hea	at exchan	ger	exch	anger	
Condition	Form	nula	Average			dry (wet) l			tlet water	
			C	limates	tem	perature (	°C)	<u> </u>	tures (°C)	
A	(-7-16)/(Tde	esignh-16)		88		-7(-8)		a /	52	
В	(+2-16)/ (To	designh-16)		54		2(1)		a /	42	
С	(+7-16)/(Tde	esignh-16)		35	7(6)			a /	36	
D	(+12-16)/(Tdesignh-16)			15		12(11)		a,	/ 30	
E	(TOL-16)/ (Tdesign		gnh-16	6)	TOL			a / 55.3		
F	(Tbivalent-16)/(Tdesignh-16) Tbiv		a /	/ 52						
G	(-15-16)/(Td		N/A		-15		N/A			
2.Tested data										
General test conditions/	Unit	A(-7)/W52 (88%)		.2/W42 (54%)	A7/W3		2/W30  5%)	A(-10)/ W55.3	A(-7)W52 (88%)	
Part-Load		(8676)	,	(34 /0)	(33 /		3 70)	(100%)	(88 %)	
		А		В	С		D	Е	F	
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	0 1:	10:00	3:00:00	3:00:00	
The heat pump defrosts		Yes		No	No		No	Yes	Yes	
Electrical Prop	erties							•		
Voltage	V	400.1		400.9	401.0	) 4	01.1	400.0	400.1	
Current input of the unit	А	5.14		2.23	1.80		1.69	5.41	5.14	
Power input of the unit	kW	2.800		1.106	0.856	6 0	.783	2.959	2.800	
Compressor	Hz	80		35	30		30	83	80	

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 14 of 59

frequency

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Test condition	s User Side						
Water flow	m³/h	0.79	0.79	0.79	0.79	0.79	0.79
Inlet Water temperature	°C	44.41	37.41	33.26	28.82	47.94	44.41
Outlet Water temperature	°C	51.46	41.91	37.82	34.11	54.67	51.46
Test condition	s Source Side						
Barometric pressure	kPa	99.85	99.85	99.85	99.80	99.75	99.85
Air <b>inlet</b> temperature, DB	°C	-6.97	2.00	7.00	12.00	-9.99	-6.97
Air <b>inlet</b> temperature, WB	°C	-7.96	1.03	6.01	10.99	-11.08	-7.96
Summary of th	e results						1
Total heating capacity	kW	6.391	4.099	4.151	4.829	6.099	6.391
Effective power input	kW	2.797	1.103	0.853	0.780	2.956	2.797
Coefficient of performance (COP)	kW/kW	2.28	3.72	4.87	6.19	2.06	2.28
Remark: * In pa	rt condition, out	tlet temperati	ure data is recor	ded by the full	average comp	lete cycle's o	lata.

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.030
Standby mode [P <sub>SB</sub> ]	kW	0.024

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.030
Standby mode [P <sub>SB</sub> ]	kW	0.024
Crankcase heater [P <sub>CK</sub> ]	kW	0.043
Off mode [P <sub>OFF</sub> ]	kW	0.024

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 15 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Tdesignh(°C):	-10		Tbiv(°C):	-7				
Pdesignh(kW):	7.225		TOL(°C):	-10				
Test result A,	B, C, D, E, F	conditions	<b>S</b> :					
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load		
E	7.225	6.099	2.06	0.90	1.00	2.06		
F	6.391	6.391	2.28	0.90	1.00	2.28		
А	6.391	6.391	2.28	0.90	1.00	2.28		
В	3.890	4.099	3.72	0.90	0.95	3.72		
С	2.501	4.151	4.87	0.90	0.60	4.56		
D	1.112	4.829	6.19	0.90	0.23	4.64		

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.64
SCOP:	kWh/kWh	3.63
Q <sub>H</sub> :	kWh/year	14927
Q <sub>HE</sub> :	kWh/year	4116
$\eta_{s,h}$	%	142.0
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 16 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Table 5.	Heating mode (Low temperature application):						Р			
Model	CGK-050V4P									
Product type	Air to Water	Heating season	<b>▽</b>	Average		Warmer		Colder		
1. Test condit	ions:									
	F	_	Outdoor			or heat				
Condition	Form	in %	Α.	(O.F.O.G.O.		at exchang			anger	
	Folii	iuia		verage imates		t dry (wet) b nperature (			tlet water tures (°C)	
А	(-7-16)/(Tde	signh-16)		88		-7(-8)		a i	/ 34	
В	(+2-16)/ (Td	lesignh-16)		54		2(1)		a /	/ 30	
С	(+7-16)/(Tde	esignh-16)		35		7(6)		a,	27	
D	(+12-16)/(Td	esignh-16)		15		12(11)		a,	/ 24	
Е	(TOL	16)/ (Tdesi	gnh-16	)		TOL		a / 35.3		
F	(Tbival	ent-16)/(Tdes	ignh-1	6)		Tbiv a / 34				
G	(-15-16)/(Tde	esignh-16)		N/A	-15 N/A				I/A	
Remark: a) With conditions, the o	capacity is 10.7	725kW, the p	ower i			-	-	en in EN1451	1-2 at 30/35	
2.Tested data	/correction o	data(Averag	je):							
General test conditions/ Part-Load	Unit	A(-7)W34 (88%)	A2W30 (54%)		A7/W2 (35%		2/W24 5%)	A(-10)/ W35.3 (100%)	A(-7)/W34 (88%)	
		А		В	С		D	Е	F	
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	00 1:	10:00	3:00:00	3:00:00	
The heat pump defrosts		Yes		No	No		No	Yes	Yes	
Electrical Prop	erties									
Voltage	V	400.6	4	401.6	401.8	3 4	01.9	400.6	400.6	
Current input of the unit	А	6.27		2.37	1.86	,	1.70	6.75	6.27	
Power input of the unit	kW	3.515		1.205	0.906	6 0	.807	3.803	3.515	
Compressor	Hz	85		35	30		30	85	85	

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 17 of 59

frequency

www.tuvsud.com

TÜV<sup>®</sup>

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Test conditions	s User Side						
Water flow	m³/h	1.82	1.82	1.82	1.82	1.82	1.82
Inlet Water temperature	°C	29.40	27.10	25.19	23.15	30.57	29.40
Outlet Water temperature	°C	33.60*	29.87	28.02	26.36	34.94*	33.60*
Test conditions	s Source Side						
Barometric pressure	kPa	101.02	101.01	101.01	101.02	101.01	101.02
Air <b>inlet</b> temperature, DB	°C	-6.99	2.01	7.03	12.00	-10.00	-6.99
Air <b>inlet</b> temperature, WB	°C	-8.00	1.03	6.03	10.99	-11.09	-8.00
Summary of th	e results						
Total heating capacity	kW	9.361	5.828	5.957	6.755	9.198	9.361
Effective power input	kW	3.508	1.198	0.899	0.800	3.796	3.508
Coefficient of performance (COP)	kW/kW	2.67	4.86	6.62	8.44	2.42	2.67

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.036
Standby mode [P <sub>SB</sub> ]	kW	0.025
Crankcase heater [P <sub>CK</sub> ]	kW	0.038
Off mode [P <sub>OFF</sub> ]	kW	0.025

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 18 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

Tel: +86 20 38320668

Doc No.: ITC-TTW0902.02E - Rev.13



3.Calculation/	conclusion f	or SCOP:							
Tdesignh(°C):	-10		Tbiv(°C):	-7	-7				
Pdesignh(kW):	10.582		TOL(°C):	-10					
Test result A,	B, C, D, E, F	conditions	<b>S</b> :	1					
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load			
E	10.582	9.198	2.42	0.90	1.00	2.42			
F	9.361	9.361	2.67	0.90	1.00	2.67			
А	9.361	9.361	2.67	0.90	1.00	2.67			
В	5.698	5.828	4.86	0.90	0.98	4.86			
С	3.663	5.957	6.62	0.90	0.61	6.23			
D	1.628	6.755	8.44	0.90	0.24	6.42			

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.72
SCOP:	kWh/kWh	4.71
Q <sub>H</sub> :	kWh/year	21862
Q <sub>HE</sub> :	kWh/year	4643
$\eta_{s,h}$	%	185.3
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Project No: 64.181.23.03037.01 Rev.: 00

Date: 2023-11-07 Page: 19 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 6.	Heating mode (Medium temperature application):								Р		
Model	CGK-050V4P										
Product type	Air to Water	Heating season	7	Average		Wa	armer		Colder		
1. Test condit	ions:	•	•								
	F	Part Load Ra	atio			Out	door		Indoo	or heat	
Condition		in %					chang		1	anger	
	Form	nula		verage imates			(wet) b ature (°			tlet water tures (°C)	
A	(-7-16)/(Tde	esianh-16)		88		•	(-8)	<u> </u>	· ·	/ 52	
В	(+2-16)/ (To			54			(1)			/ 42	
С	(+7-16)/(Tde			35			(6)		a i	<sup>/</sup> 36	
D	(+12-16)/(Td			15			(11)		a /	/ 30	
E	(TOL	gnh-16	5)		Т	OL		a/	55.3		
F	(Tbival	ent-16)/(Tdes	signh-1	16)	Tbiv			a / 52			
G	(-15-16)/(Td	esignh-16)		N/A	-15				N/A		
Remark: a) With conditions, the conditions at 2.Tested data	capacity is 9.60	31kW, the po	wer is			-		_	n in EN1451	1-2 at 47/55	
	•			0.14.40	A 744/	20	A 40	11100	A ( 4 0) (	A ( 7) AA(50	
General test conditions/ Part-Load	Unit	A(-7)W52 (88%)		2/W42 (54%)	A7/W3 (35%			W30 5%)	A(-10)/ W55.3 (100%)	A(-7)/W52 (88%)	
		А		В	С			D	Е	F	
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	00	1:1	0:00	1:10:00	3:00:00	
The heat pump defrosts		Yes		No	No		١	No.	No	Yes	
Electrical Prop	erties										
Voltage	V	400.4		401.6	401.	7	40	1.8	400.3	400.4	
Current input of the unit	А	6.57		2.87	2.27	,	2	.05	7.81	6.57	
Power input of the unit	kW	3.765		1.478	1.124	4	0.9	996	4.501	3.765	
Compressor	Hz	85		35	30		-	30	85	85	

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 20 of 59

frequency

www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Test condition	s User Side						
Water flow	m³/h	1.04	1.04	1.04	1.04	1.04	1.04
Inlet Water temperature	°C	44.60	37.47	33.22	28.68	47.38	44.60
Outlet Water temperature	°C	51.72*	42.01	37.82	34.00	55.11	51.72*
Test condition	s Source Side						
Barometric pressure	kPa	99.85	99.85	99.85	99.80	99.75	99.85
Air <b>inlet</b> temperature, DB	°C	-6.99	2.01	7.00	12.00	-9.99	-6.99
Air <b>inlet</b> temperature, WB	°C	-7.94	1.03	6.01	10.99	-11.08	-7.94
Summary of th	e results						
Total heating capacity	kW	8.505	5.429	5.528	6.387	9.222	8.505
Effective power input	kW	3.761	1.474	1.120	0.992	4.496	3.761
Coefficient of performance (COP)	kW/kW	2.26	3.68	4.93	6.44	2.05	2.26

Remark: \* In part condition, outlet temperature data is recorded by the full average complete cycle's data.

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.036
Standby mode [P <sub>SB</sub> ]	kW	0.025
Crankcase heater [P <sub>CK</sub> ]	kW	0.038
Off mode [P <sub>OFF</sub> ]	kW	0.025

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 21 of 59 www.tuvsud.com

TÜV<sup>®</sup>

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



3.Calculation/	conclusion f	or SCOP:						
Tdesignh(°C):	-10		Tbiv(°C):	-7				
Pdesignh(kW):	9.615		TOL(°C):	-10				
Test result A,	B, C, D, E, F	conditions	s:					
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load		
Е	9.615	9.222	2.05	0.90	1.00	2.05		
F	8.505	8.505	2.26	0.90	1.00	2.26		
А	8.505	8.505	2.26	0.90	1.00	2.26		
В	5.177	5.429	3.68	0.90	0.95	3.68		
С	3.328	5.528	4.93	0.90	0.60	4.63		
D	1.479	6.387	6.44	0.90	0.23	4.84		
CR: part load di	vided by capac	ity;		1				

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.65
SCOP:	kWh/kWh	3.64
Q <sub>H</sub> :	kWh/year	19864
Q <sub>HE</sub> :	kWh/year	5458
$\eta_{s,h}$	%	142.6
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 22 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 7.	Heating mode (Low temperature application):							Р		
Model	CGK-060V4P									
Product type	Air to Water	Heating season	7	Average		Warme	er 🗆		Colder	
1. Test condit	ions:									
	F	Part Load Ra	itio		hor	Outdoo at excha				or heat
Condition	Form			verage imates	Inlet	dry (wet	) bulb		exchanger Inlet/outlet water temperatures (°C)	
А	(-7-16)/(Tde	signh-16)		88		-7(-8)			a /	34
В	(+2-16)/ (Td	lesignh-16)		54		2(1)			a /	' 30
С	(+7-16)/(Tde	esignh-16)		35		7(6)			a /	27
D	(+12-16)/(Td	esignh-16)		15		12(11)			a /	24
E	(TOL	16)/ (Tdesi	gnh-16	)		TOL			a/:	35.3
F	(Tbival	ent-16)/(Tdes	ignh-1	6)	Tbiv			a / 34		
G	(-15-16)/(Tde	esignh-16)		N/A	-15				N/A	
Remark: a) With conditions, the conditions at a conditions.	capacity is 12.8	306kW, the p	ower i			-	_		n in EN1451	1-2 at 30/35
General test conditions/ Part-Load	Unit	A(-7)W34 (88%)	A2/W30 (54%)		A7/W2 (35%		12/W24 (15%)	ļ	A(-10)/ W35.3 (100%)	A(-7)W34 (88%)
		А		В	С		D		E	F
Data collection period	hh: min:sec	3:00:00	1	:10:00	1:10:0	0	1:10:00		3:00:00	3:00:00
The heat pump defrosts		Yes		No	No		No		Yes	Yes
Electrical Prop	erties									
Voltage	V	400.5	4	400.0	401.7	7	401.8		400.5	400.5
Current input of the unit	А	6.81		2.84	2.27		2.02	6.95 6		6.81
Power input of the unit	kW	3.876		1.410	1.129	9	0.985		3.965 3.876	
Compressor frequency	Hz	85		35	30		30		85	85

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 23 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Test conditions	s User Side						
Water flow	m³/h	2.20	2.20	2.20	2.20	2.20	2.20
Inlet Water temperature	°C	29.14	27.18	25.26	23.23	30.55	29.14
Outlet Water temperature	°C	33.56*	29.88	28.06	26.38	34.95*	33.56*
Test conditions	s Source Side						
Barometric pressure	kPa	101.02	101.01	101.01	101.02	101.01	101.02
Air <b>inlet</b> temperature, DB	°C	-6.94	2.01	7.01	12.01	-9.94	-6.94
Air <b>inlet</b> temperature, WB	°C	-7.95	1.00	6.01	10.99	-10.96	-7.95
Summary of th	e results						
Total heating capacity	kW	11.235	6.894	7.113	8.023	11.178	11.235
Effective power input	kW	3.869	1.403	1.122	0.978	3.957	3.869
Coefficient of performance (COP)	kW/kW	2.90	4.92	6.34	8.21	2.82	2.90

Remark: * In part condition	i, outlet temperature data is	s recorded by the full aver	age complete cycle's data.
-----------------------------	-------------------------------	-----------------------------	----------------------------

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.035
Standby mode [P <sub>SB</sub> ]	kW	0.025
Crankcase heater [P <sub>CK</sub> ]	kW	0.039
Off mode [P <sub>OFF</sub> ]	kW	0.025

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 24 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch



3.Calculation/conclusion for SCOP:								
Tdesignh(°C):	-10		Tbiv(°C):	-7				
Pdesignh(kW):	12.700		TOL(°C):	-10				
Test result A, B, C, D, E, F conditions:								
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load		
Е	12.700	11.178	2.82	0.90	1.00	2.82		
F	11.235	11.235	2.90	0.90	1.00	2.90		
А	11.235	11.235	2.90	0.90	1.00	2.90		
В	6.838	6.894	4.92	0.90	0.99	4.92		
С	4.396	7.113	6.34	0.90	0.62	5.97		
D	1.954	8.023	8.21	0.90	0.24	6.26		

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.77
SCOP:	kWh/kWh	4.76
Q <sub>H</sub> :	kWh/year	26238
Q <sub>HE</sub> :	kWh/year	5510
$\eta_{s,h}$	%	187.5
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 25 of 59 www.tuvsud.com

TÜV<sup>®</sup>

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Table 8.	Heating mode (Medium temperature application):						!	P		
Model	CGK-060V4P	CGK-060V4P								
Product type	Air to Water	Heating season	<b>V</b>	Average		Warme	r 🗆	Colder		
1. Test condit	ions:									
	F	Part Load Ra	atio			Outdoo			r heat	
Condition	Гания	in %	۸.			at exchar	_	1	anger	
	Form	iuia		verage imates		dry (wet) perature			tlet water tures (°C)	
А	(-7-16)/(Tde	signh-16)		88		-7(-8)		a /	52	
В	(+2-16)/ (Td	esignh-16)		54		2(1)		a /	42	
С	(+7-16)/(Tde	esignh-16)		35		7(6)		a /	36	
D	(+12-16)/(Td	esignh-16)		15		12(11)		a /	' 30	
E	(TOL	16)/ (Tdesi	gnh-16	)		TOL		a/	55.3	
F	(Tbivale	ent-16)/(Tdes	ignh-1	6)	Tbiv		a / 52			
G	(-15-16)/(Tde	esignh-16)		N/A	-15		N/A			
Remark: a) With conditions, the o	capacity is 11.4	189kW, the p	ower i			-	-	n in EN1451	1-2 at 47/55	
2.Tested data		lata(Averag	je):							
General test conditions/ Part-Load	Unit	A(-7)W52 (88%)		2/W42 54%)	A7/W3 (35%		12/W30 (15%)	A(-10)/ W55.3 (100%)	A(-7)W52 (88%)	
		Α		В	С		D	E	F	
Data collection period	hh: min:sec	3:00:00	1:	:10:00	1:10:0	00 1	:10:00	1:10:00	3:00:00	
The heat pump defrosts		Yes		No	No		No	No	Yes	
Electrical Prop	erties									
Voltage	V	400.0	4	401.4	401.7	7	401.7	400.0	400.0	
Current input of the unit	А	8.14		3.23	2.58		2.39	8.41	8.14	
Power input of the unit	kW	4.743		1.691	1.311	ı	1.184	4.924	4.743	
Compressor frequency	Hz	84		35	30		30	85	84	


Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 26 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Test conditions User Side								
Water flow	m³/h	1.25	1.25	1.25	1.25	1.25	1.25	
Inlet Water temperature	°C	44.27	37.52	33.22	28.58	48.01	44.27	
Outlet Water temperature	°C	51.48*	41.98	37.78	33.82	55.10	51.48*	
Test condition	s Source Side							
Barometric pressure	kPa	99.85	99.85	99.85	99.80	99.75	99.85	
Air <b>inlet</b> temperature, DB	°C	-6.95	2.00	7.00	12.00	-9.99	-6.95	
Air <b>inlet</b> temperature, WB	°C	-7.92	1.03	6.01	11.00	-10.92	-7.92	
Summary of th	Summary of the results							
Total heating capacity	kW	10.359	6.417	6.567	7.570	10.164	10.359	
Effective power input	kW	4.738	1.686	1.306	1.179	4.919	4.738	
Coefficient of performance (COP)	kW/kW	2.19	3.81	5.03	6.42	2.07	2.19	

Remark: \* In part condition, outlet temperature data is recorded by the full average complete cycle's data.

Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.035
Standby mode [P <sub>SB</sub> ]	kW	0.025
Crankcase heater [P <sub>CK</sub> ]	kW	0.039
Off mode [P <sub>OFF</sub> ]	kW	0.025

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 27 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



3.Calculation/	conclusion f	for SCOP:						
Tdesignh(°C):	-10		Tbiv(°C):	-7				
Pdesignh(kW):	11.710		TOL(°C):	-10				
Test result A, B, C, D, E, F conditions:								
Condition	Part load	Measured capacity	Measured COP	Cdh	CR	COP at part load		
E	11.710	10.164	2.07	0.90	1.00	2.07		
F	10.359	10.359	2.19	0.90	1.00	2.19		
А	10.359	10.359	2.19	0.90	1.00	2.19		
В	6.305	6.417	3.81	0.90	0.98	3.81		
С	4.053	6.567	5.03	0.90	0.62	4.73		
D	1.801	7.570	6.42	0.90	0.24	4.86		

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.70
SCOP:	kWh/kWh	3.69
Q <sub>H</sub> :	kWh/year	24192
Q <sub>HE</sub> :	kWh/year	6550
$\eta_{s,h}$	%	144.7
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 28 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Sound power level	Р							
CGK-030V4P	CGK-030V4P							
Product type :			Air to Water					
Outdoor heat exchar	nger, Air temperature [	DB/WB (°C):	7.0 / 6.0					
Indoor heat exchang	er, Water inlet/outlet te	emperature (°C):	30.0 / 35.0					
Voltage (V):			400					
Frequency (Hz):	Frequency (Hz):							
Working condition cl	Class A							
Acoustical environme	Hemi-anechoic room							
Windshield type:			Sponge					
Measured position a	mount :		14					
Water flow (m³/h):			1.31					
sured quantity	L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark					
sure level $\overline{L}_{p(ST)}^{****}$		46						
ent distance d *		1.0m						
er level L <sub>wA</sub> ****		60						
	CGK-030V4P  Product type:  Outdoor heat exchange   Voltage (V):  Frequency (Hz):  Working condition classed and type:  Measured position and   Water flow (m³/h):  sured quantity  sure level   \( \bar{L}_{p(ST)}^{****} \)	CGK-030V4P  Product type:  Outdoor heat exchanger, Air temperature E  Indoor heat exchanger, Water inlet/outlet te  Voltage (V):  Frequency (Hz):  Working condition class:  Acoustical environment:  Windshield type:  Measured position amount:  Water flow (m³/h):  Sured quantity  Sure level \( \bar{L}_{p(ST)}^{****} \)  ent distance d *	Product type:  Outdoor heat exchanger, Air temperature DB/WB (°C):  Indoor heat exchanger, Water inlet/outlet temperature (°C):  Voltage (V):  Frequency (Hz):  Working condition class:  Acoustical environment:  Windshield type:  Measured position amount:  Water flow (m³/h):  Sured quantity  LwA,indoors (dB(A))  LwA,outdoors (dB(A))  sure level Lp(ST)****  46  ent distance d * 1.0m					

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 590 r/min, compressor frequency: 58Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 29 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 9b.	Sound power level	P		
Model	CGK-030V4P			
	Product type :			Air to Water
	Outdoor heat exchar	nger, Air temperature D	DB/WB (°C):	7.0 / 6.0
	Indoor heat exchang	er, Water inlet/outlet te	emperature (°C):	47.0 / 55.0
	Voltage (V):			400
	Frequency (Hz):			50
	Working condition cl		Class A	
	Acoustical environme	ent :		Hemi-anechoic room
	Windshield type :		Sponge	
	Measured position a	mount :	14	
	Water flow (m³/h):		0.75	
Mea	sured quantity	L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark
Sound pres	sure level $\overline{L}_{p(ST)}^{****}$		47	
Measureme	ent distance d *		1.0m	
Sound pow	er level L <sub>wA</sub> ****		60	
-	er level L <sub>wA</sub> ****		60	

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 580 r/min, compressor frequency: 58Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 30 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 10a.	Sound power level measurement (Low temperature application)			Р	
Model	CGK-040V4P				
	Product type :			Air to Water	
	Outdoor heat exchanger, Air temperature DB/WB (°C): Indoor heat exchanger, Water inlet/outlet temperature (°C):			7.0 / 6.0	
				30.0 / 35.0	
	Voltage (V):			400	
Frequency (Hz):				50	
	Working condition class :			Class A	
	Acoustical environme	ent :		Hemi-anechoic room	
	Windshield type:			Sponge	
Measured position a Water flow (m³/h):		mount :		14	
				1.40	
Measured quantity L <sub>WA,ir</sub>		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark	
Sound pressure level $\overline{L}_{p(ST)}^{****}$			47		
Measurement distance d *			1.0m		
Sound power level L <sub>wA</sub> ****			62		

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 590 r/min, compressor frequency: 64Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 31 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 10b.	Sound power level measurement (Medium temperature application)			P	
Model	CGK-040V4P				
	Product type:  Outdoor heat exchanger, Air temperature DB/WB (°C):  Indoor heat exchanger, Water inlet/outlet temperature (°C):			Air to Water	
				7.0 / 6.0	
				47.0 / 55.0	
	Voltage (V):				
	Frequency (Hz):			50	
	Working condition class:			Class A	
	Acoustical environme	ent:		Hemi-anechoic room	
Windshield type:  Measured position a		amount :		Sponge	
				14	
Wat	Water flow (m³/h):	low (m³/h):			
Measured quantity		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark	
Sound pressure level $\overline{L}_{p(ST)}^{****}$			45		
Measurement distance d *			1.0m		
Sound power level L <sub>wA</sub> ****			60		
O 11: 1	entrola: according to u			<u>I</u>	

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 530 r/min, compressor frequency: 56Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 32 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 11a.	Sound power level measurement (Low temperature application)			Р	
Model	CGK-050V4P				
	Product type:  Outdoor heat exchanger, Air temperature DB/WB (°C):  Indoor heat exchanger, Water inlet/outlet temperature (°C):			Air to Water	
				7.0 / 6.0	
				30.0 / 35.0	
	Voltage (V):			400	
Frequency (Hz):				50	
	Working condition class :			Class A	
	Acoustical environme	ent :		Hemi-anechoic room	
	Windshield type:			Sponge	
Measured position a Water flow (m³/h):		mount :		14	
				1.82	
Measured quantity L <sub>WA,inc</sub>		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark	
Sound pressure level $\overline{L}_{p(ST)}^{****}$			46		
Measurement distance d *			1.0m		
Sound power level L <sub>wA</sub> ****			60		

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 518 r/min, compressor frequency: 60Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 33 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 11b.	Sound power level measurement (Medium temperature application)			P
Model	CGK-050V4P			
	Product type:  Outdoor heat exchanger, Air temperature DB/WB (°C):  Indoor heat exchanger, Water inlet/outlet temperature (°C):			Air to Water
				7.0 / 6.0
				47.0 / 55.0
	Voltage (V):			400
	Frequency (Hz):			50
	Working condition class:			Class A
	Acoustical environme	ent :		Hemi-anechoic room
Windshield type:  Measured position a		amount :		Sponge
				14
Water fl	Water flow (m³/h):		1.04	
Measured quantity		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark
Sound pressure level $\overline{L}_{p(ST)}^{****}$			47	
Measurement distance d *			1.0m	
Sound power level L <sub>wA</sub> ****			62	
<u> </u>	entrole: according to u			

Setting of controls: according to user manual.

Duct connection: --

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 490 r/min, compressor frequency: 60Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 34 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 12a.	Sound power level measurement (Low temperature application)			Р	
Model	CGK-060V4P				
	Product type :				
	Outdoor heat exchanger, Air temperature DB/WB (°C): Indoor heat exchanger, Water inlet/outlet temperature (°C):			7.0 / 6.0	
				30.0 / 35.0	
	Voltage (V):			400	
Frequency (Hz):				50	
	Working condition class:			Class A	
	Acoustical environme	ent :		Hemi-anechoic room	
	Windshield type:			Sponge	
Measured position a Water flow (m³/h):		mount :		14	
				2.20	
Measured quantity		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark	
Sound pressure level $\overline{L}_{p(ST)}^{****}$			46		
Measurement distance d *			1.0m		
Sound power level L <sub>wA</sub> ****			61		

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 490 r/min, compressor frequency: 60Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 35 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# **Appendix I Test results**

Table 12b.	Sound power level measurement (Medium temperature application)			P	
Model	CGK-060V4P				
	Product type :		Air to Water		
Outdoor heat exchanger, Air temperature DB			B/WB (°C):	7.0 / 6.0	
	Indoor heat exchanger, Water inlet/outlet temperature (°C):			47.0 / 55.0	
	Voltage (V):			400	
	Frequency (Hz):			50	
	Working condition class :			Class A	
	Acoustical environme	ent:		Hemi-anechoic room	
Windshield type :  Measured position		amount :		Sponge	
				14	
Water	Water flow (m³/h):		1.25		
Measured quantity L <sub>WA,indoors</sub> (dB(A)) L <sub>WA,outdoors</sub> (dB(		L <sub>WA,outdoors</sub> (dB(A))	Remark		
Sound pressure level $\bar{L}_{p(ST)}^{****}$			46		
Measurement distance d *			1.0m		
Sound power level L <sub>wA</sub> ****			61		

Setting of controls: according to user manual.

Duct connection: --

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 480 r/min, compressor frequency: 60Hz.

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 36 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Table 13.	3. Clause 4 of EN 14511-4:2022	
Model:	CGK-030V4P	
TEST 1	STARTING TEST (§4.2.1.2 Table 3)	

Requirement: The "lower" starting operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -24.76 °C, T in water = 9.97 °C, Flow rate 0.68 m³/h have been set and obtained. At those conditions, the machine was switched on.

Observation/ Evaluation: It started without any problem and worked for 30 minutes without showing any warning or alarm. During the test the machine operated in auto mode. No damage was recorded on the machine during and after the test.

Test Response: Pass

# TEST 2 OPERATING TEST (§4.2.1.2 Table 3)

Requirement: From the machine "lower" starting conditions - i.e. - the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.00 °C, T in water = 52.00 °C, Flow rate 0.68 m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in auto mode.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 3 SHUTTING OFF WATER FLOW (§ 4.5)

Requirement: The water flow rate was shuted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit.

Observation/ Evaluation: Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 4 SHUTTING OFF AIR FLOW (§ 4.5)

Requirement: The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 5 COMPLETE POWER SUPPLY FAILURE (§ 4.6)

Requirement: The power supply was cut off for about 5 seconds.

Observation/ Evaluation: The unit restarted automatically within about 3 minutes after the power supply was reactivated.

Test Response: Pass

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 37 of 59 www.tuvsud.com

D

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 14.	4. Clause 4 of EN 14511-4:2022 P	
Model:	CGK-040V4P	
TEST 1	STARTING TEST (§4.2.1.2 Table 3)	

Requirement: The "lower" starting operating conditions declared by the manufacturer for the heating mode-i.e. Tair= -25.07 °C, T in water = 9.27 °C, Flow rate 0.71 m³/h have been set and obtained. At those conditions, the machine was switched on.

Observation/ Evaluation: It started without any problem and worked for 30 minutes without showing any warning or alarm. During the test the machine operated in auto mode. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 2 OPERATING TEST (§4.2.1.2 Table 3)

Requirement: From the machine "lower" starting conditions - i.e. - the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.00 °C, T in water = 51.13 °C, Flow rate 0.71 m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in auto mode.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 3 SHUTTING OFF WATER FLOW (§ 4.5)

Requirement: The water flow rate was shuted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit.

Observation/ Evaluation: Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 4 SHUTTING OFF AIR FLOW (§ 4.5)

Requirement: The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 5 | COMPLETE POWER SUPPLY FAILURE (§ 4.6)

Requirement: The power supply was cut off for about 5 seconds.

Observation/ Evaluation: The unit restarted automatically within about 3 minutes after the power supply was reactivated.

Test Response: Pass

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 38 of 59 www.tuvsud.com

)

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 15.	5. Clause 4 of EN 14511-4:2022 P	
Model:	CGK-050V4P	
TEST 1	STARTING TEST (§4.2.1.2 Table 3)	

Requirement: The "lower" starting operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.02 °C, T in water = 8.60 °C, Flow rate 0.93 m³/h have been set and obtained. At those conditions, the machine was switched on.

Observation/ Evaluation: It started without any problem and worked for 30 minutes without showing any warning or alarm. During the test the machine operated in auto mode. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 2 OPERATING TEST (§4.2.1.2 Table 3)

Requirement: From the machine "lower" starting conditions - i.e. - the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.00  $^{\circ}$ C, T in water = 50.89  $^{\circ}$ C, Flow rate 0.93 m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in auto mode.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 3 SHUTTING OFF WATER FLOW (§ 4.5)

Requirement: The water flow rate was shuted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit.

Observation/ Evaluation: Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 4 SHUTTING OFF AIR FLOW (§ 4.5)

Requirement: The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 5 COMPLETE POWER SUPPLY FAILURE (§ 4.6)

Requirement: The power supply was cut off for about 5 seconds.

Observation/ Evaluation: The unit restarted automatically within about 3 minutes after the power supply was reactivated.

Test Response: Pass

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 39 of 59 www.tuvsud.com

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Table 16.	6. Clause 4 of EN 14511-4:2022 P	
Model:	CGK-060V4P	
TEST 1	STARTING TEST (§4.2.1.2 Table 3)	

Requirement: The "lower" starting operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.05 °C, T in water = 8.48 °C, Flow rate 1.12 m³/h have been set and obtained. At those conditions, the machine was switched on.

Observation/ Evaluation: It started without any problem and worked for 30 minutes without showing any warning or alarm. During the test the machine operated in auto mode. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 2 OPERATING TEST (§4.2.1.2 Table 3)

Requirement: From the machine "lower" starting conditions - i.e. - the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair= -25.00  $^{\circ}$ C, T in water = 50.68  $^{\circ}$ C, Flow rate 1.12 m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in auto mode.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 3 SHUTTING OFF WATER FLOW (§ 4.5)

Requirement: The water flow rate was shuted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit.

Observation/ Evaluation: Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.

Test Response: Pass

#### TEST 4 SHUTTING OFF AIR FLOW (§ 4.5)

Requirement: The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally.

Observation/ Evaluation: During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.

Test Response: Pass

### TEST 5 COMPLETE POWER SUPPLY FAILURE (§ 4.6)

Requirement: The power supply was cut off for about 5 seconds.

Observation/ Evaluation: The unit restarted automatically within about 3 minutes after the power supply was reactivated.

Test Response: Pass

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 40 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China








#### Nameplate

Model: CGK-030V4P



Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 41 of 59 www.tuvsud.com



TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch


5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





#### Nameplate

Model: CGK-040V4P



Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 42 of 59





TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch


5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





### Nameplate

Model: CGK-050V4P



Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 43 of 59 www.tuvsud.com



TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch


5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





#### Nameplate

Model: CGK-060V4P



Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 44 of 59

www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Details of:	Overall view for CGK-030V4P
View:  General Front Rear Right Left Top Bottom	

View: Panasonic
General

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 45 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

# **Technical Report**



# Appendix III photo documentation

Details of:	Fan Motor for CGK-030V4P
View:  General Front Rear Right Left Top Bottom	WOLONG PROMITED TO THE PROMITED PROMIT

Details of:	Main Control Board for CGK-030V4P
View:  ☐ General	
☐ Front	
☐ Rear	
☐ Right	
□ Left	Comercial Commercial C
□ Тор	
□ Bottom	

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 46 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Details of:	Water Pump for CGK-030V4P
View:  General Front Rear Right Left Top Bottom	GRUNDFOS  UPM4XL K 25-90 130

Overall view for CGK-040V4P
Cheveliteretiteretiteretiteretine
The state of the s
33 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
A STATE OF THE STA

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 47 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Details of:	Compressor for CGK-040V4P
View:  General Front Rear Right Left Top Bottom	Panasonic H420D7KZAAC6  COMPRESSOR DC MOTOR 280V —— SERIAL NO. K42W F0000033 7975739 R290 Panasonic Corporation 松下. 万宝 (广州) 压缩机有限公司 Made in China Panasonic Wanbao Appliances Compressor (Guangzhou) Co., Ltd. 36. Wanbao North Street, Wanbao Industry Zone, Zhongcun, Panyu District, Guangzhou City, Guangdong Province, China  WARNING/DANGER 注意 (维修、检查时必须通守)  A Danger S. E. A. Danger D. Da

Details of:		Fan Motor for CGK-040V4P
View:		
☐ Genera	al	WOLONG 空调用无刷直流电动机 ZWB278D04A(1821300) DC310V 查 (BU) FG ROHS
☐ Front		102W 8P 920r/min
☐ Rear		D 龙电气驱动集团股份有限公司 WOLONG ELECTRIC GROUP CO.,LTD.
☐ Right		SILOUP CO., LIB.
☐ Left		
□ Тор		
□ Bottom		

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-

Date: 2023-11-07 Page: 48 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch



Details of:	Main Control Board for CGK-040V4P
View:  General Front Rear Right Left Top Bottom	in the second se

Details of:	Water Pump for CGK-040V4P
View:  General  Front  Rear  Right  Left  Top  Bottom	GRUNDFOS  UPM4XL K 25-90 130

Doc No.: ITC-TTW0902.02E - Rev.13

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 49 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Details of:	Overall view for CGK-050V4P
View:  General  Front Rear Right Left Top Bottom	The same of the sa
□ Left □ Top	Read Read Read Read Read Read Read Read

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 50 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

# **Technical Report**



# Appendix III photo documentation

Details of:	Fan Motor for CGK-050V4P
View:	
☐ General	WOLONG A用 无 新 章 电 动 机 QC.PASS \$ RoHS \$
☐ Front	102W 8P 920r/min M = (BK) GND
☐ Rear	IP24 E级 红 (RD) Vm 龙电气驱动集团股份有限公司 WOLONG ELECTRIC GROUP CO.,LTD.
☐ Right	
☐ Left	
□ Тор	
☐ Bottom	

View:  General  Front  Rear  Right  Top  Bottom	 Main Control Board for CGK-050V4P	ails of:	Det
□ Front □ Rear □ Right □ Left □ Top □ Bottom	• • •	w:	Vie
□ Rear □ Right □ Left □ Top □ Bottom		General	
□ Right □ Left □ Top □ Bottom		Front	
□ Right □ Left □ Top □ Bottom		Rear	
□ Top □ Bottom		Right	
Bottom	The state of the s	Left	
		Тор	
		Bottom	
The state of the s			

Project No: 64.181.23.03037.01

Rev.: 00

Doc No.: ITC-TTW0902.02E - Rev.13

Date: 2023-11-07 Page: 51 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

# **Technical Report**



# Appendix III photo documentation

Details of:	Water Pump for CGK-050V4P	
View:		
☐ General	GRUNDFOSX 6	
☐ Front	UPM10L 25-105 130	
☐ Rear		
Right	EEL < 0.20 - Part 3 Plans < 82WV 230V ~ 50/80HzHz /PX/4D TF-110 GFBSA Min 20°C P/N:33032863 PC:2335CHU	
□ Left	Made in Denmark Street St. (1950 Specially A.13 Made in Denmark Street St. (1950 Specially A.13 Manual)	
□ Тор	C€ .	
☐ Bottom		

Details of:	Overall view for CGK-060V4P
View:	ু <mark>ব্যৱহার ব্যৱহার বিষয় কর্ম কর্ম কর্ম কর্ম কর্ম কর্ম কর্ম কর্ম</mark>
☐ General	The state of the s
☐ Front	Trinning Control of the Control of t
□ Rear	D. Control of the Con
□ Right	Constant of the Constant of th
☐ Left	Research Control of the Control of t
□ Тор	N. S. C.
☐ Bottom	The state of the s
	Section 12 man

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 52 of 59

www.tuvsud.com



 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Details of:	Compressor for CGK-060V4P
View:	Panasonic H650D7VZAAC6
☐ Front	COMPRESSOR
☐ Rear	DC MOTOR 520V SERIAL NO. V65Z
☐ Right	F9999997 7975741 R290
□ Left	松 ト・万宝(广州) 圧縮机有限公司 Made in China 🔙 🔙 🗧
□ Тор	Panasonic Wanbao Appliances Compressor (Guangzhou) Co., Ltd.  36, Wanbao North Street, Wanbao Industry Zone, Zhongcun, Panyu District On China
☐ Bottom	Panyu District, GuangZhou City, Guangdong Province, China  WARNING/DANGER 注意(维修, 检查时必须遵守)

Details of:	Fan Motor for CGK-060V4P
View:	00
☐ General	WOLONG AIR Conditioner LED Lot (BU) FG ROHS ROHS ROHS ROHS ROHS ROHS
☐ Front	ZWB278D04A(1821300) DC310V 102W 8P 920r/min M 自 (WH) VCC 日本に多る第
☐ Rear	P24 E级  D 龙电气驱动集团股份有限公司 WOLONG ELECTRIC GROUP CO.,LTD.
☐ Right	WOLONG ELECTRIC GROUP CO., E. S.
☐ Left	
□ Тор	
□ Bottom	

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07

Doc No.: ITC-TTW0902.02E - Rev.13

Page: 53 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



View:  General  Front  Rear  Right  Left  Top  Bottom	Details of:	Main Control Board for CGK-060V4P
Name (General)	View:  General  Front Rear Right Left Top	

Details of:	Water Pump for CGK-060V4P	
View:		
☐ General	GRUNDFOS X  UPM10L 25-105 130 - Thy(A)   P1(W)   MPa	
☐ Front	Min. 0.05 3 Max. 1.1 140 1.0	
☐ Rear	EEI & 0.20 - Part 3 Page & 82VW 230V ~ 50/60HzHz IPXAD TF110 GFBSA Min20°C P/N:93032863 PC:2335CHU	
☐ Right	Name in Denmark Studies Not St. 23335110	
☐ Left	C€	
□ Тор		
☐ Bottom		

Project No: 64.181.23.03037.01

Rev.: 00

Date: 2023-11-07 Page: 54 of 59

www.tuvsud.com

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Part		Technical data		
1. Compressor				
	Manufacture:	Panasonic Wanbao Appliances Compressor		
		(Guangzhou) Co. , Ltd.		
	Type:	H420D7KZAAC6		
	Rated capacity:	2245W		
	Serial-number:	F0000030		
	Specification:	DC280V; R290		
2. Condenser				
	Manufacture:	Jiangsu Yuanzhuo Equipment Manfactur Co.,Ltd		
	Type:	ZL62FA-26AD-CG		
	Heat exchanger:	Plate heat exchanger		
	Dimension(mm):	526(L)mmX119(H)mmX63(D)mm		
3. Evaporator				
	Manufacture:	Guangzhou Aotai Refrigeration Equipment Co.,Ltd.		
	Type:	03KH-CP-01		
	Heat exchanger:	Finned-coil heat exchanger		
	Dimension(mm):	660(L)mmX750(H)mmX356.8(D)mm		
4. Fan motor				
	Manufacture:	Wolong Electric Group Co., Ltd		
	Type:	ZWB278D04A		
	Fan type:	3 blade		
	Specification:	DC310V; 102W		
5. Main control board				
	Manufacture:	CAREL		
	Type:	UP3F00200T3S04		
	Specification:	220-240V~; 50Hz		
6. Water pump				
	Manufacture:	GRUNDFOS		
	Type:	UPM4XL K 25-90 130		
	Specification:	230V~; 50/60Hz		
*(Alternative)				
	Manufacture:	Shinhoo		
	Type:	GPA25-9HW		
	Specification:	230V~; 50/60Hz		

Remark: \* means the test results were not performed on the alternative components.

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 55 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Part		Technical data		
1. Compressor				
<u> </u>	Manufacture:	Panasonic Wanbao Appliances Compressor		
		(Guangzhou) Co. • Ltd.		
	Type:	H420D7KZAAC6		
	Rated capacity:	2245W		
	Serial-number:	F0000033		
	Specification:	DC280V; R290		
2. Condenser				
	Manufacture:	Jiangsu Yuanzhuo Equipment Manfactur Co.,Ltd		
	Type:	ZL62FA-30AD-CG		
	Heat exchanger:	Plate heat exchanger		
	Dimension(mm):	526(L)mmX119(H)mmX71(D)mm		
3. Evaporator				
	Manufacture:	Guangzhou Aotai Refrigeration EquipmentCo.,Ltd.		
	Type:	04KH-CP-01		
	Heat exchanger:	Finned-coil heat exchanger		
	Dimension(mm):	660.4(L)mmX900(H)mmX343.3(D)mm		
4. Fan motor				
	Manufacture:	Wolong Electric Group Co., Ltd		
	Type:	ZWB278D04A		
	Fan type:	3 blade		
	Specification:	DC310V; 102W		
5. Main control board				
	Manufacture:	CAREL		
	Type:	UP3F00200T3S04		
	Specification:	220-240V~; 50Hz		
6. Water pump				
	Manufacture:	GRUNDFOS		
	Type:	UPM4XL K 25-90 130		
	Specification:	230V~; 50/60Hz		
*(Alternative)				
	Manufacture:	Shinhoo		
	Type:	GPA25-9HW		
	Specification:	230V~; 50/60Hz		

Remark: \* means the test results were not performed on the alternative components.

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 56 of 59 www.tuvsud.com

TÜV<sup>®</sup>

 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China





Part		Technical data	
1. Compressor		10011110411	
<u> </u>	Manufacture:	Panasonic Wanbao Appliances Compressor	
		(Guangzhou) Co. 💂 Ltd.	
	Type:	H550D7VZAAC6	
	Rated capacity:	3120W	
	Serial-number:	F999997	
	Specification:	DC520V; R290	
2. Condenser			
	Manufacture:	Jiangsu Yuanzhuo Equipment Manfactur Co.,Ltd	
	Type:	ZL62FA-40AD-CG	
	Heat exchanger:	Plate heat exchanger	
	Dimension(mm):	526(L)mmX119(H)mmX91(D)mm	
3. Evaporator			
	Manufacture:	Guangzhou Aotai Refrigeration Equipment Co.,Ltd.	
	Type:	05KH-CP-01	
	Heat exchanger:	Finned-coil heat exchanger	
	Dimension(mm):	660.4(L)mmX1300(H)mmX343.3(D)mm	
4. Fan motor			
	Manufacture:	Wolong Electric Group Co., Ltd	
	Type:	ZWB278D04A	
	Fan type:	3 blade	
	Specification:	DC310V; 102W	
5. Main control board			
	Manufacture:	CAREL	
	Type:	UP3F00200T3S04	
	Specification:	220-240V~; 50Hz	
6. Water pump			
	Manufacture:	GRUNDFOS	
	Type:	UPM10L 25-105 130	
	Specification:	230V~; 50/60Hz	
*(Alternative)			
	Manufacture:	Shinhoo	
	Type:	GPA25-11H	
	Specification:	230V~; 50Hz	

Remark: \* means the test results were not performed on the alternative components.

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 57 of 59

www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Part		Technical data		
1. Compressor				
	Manufacture:	Panasonic Wanbao Appliances Compressor		
		(Guangzhou) Co. , Ltd.		
	Type:	H650D7VZAAC6		
	Rated capacity:	3640W		
	Serial-number:	F999997		
	Specification:	DC520V; R290		
2. Condenser				
	Manufacture:	Jiangsu Yuanzhuo Equipment Manfactur Co.,Ltd		
	Type:	ZL62FA-40AD-CG		
	Heat exchanger:	Plate heat exchanger		
	Dimension(mm):	526(L)mmX119(H)mmX91(D)mm		
3. Evaporator				
	Manufacture:	Guangzhou Aotai Refrigeration Equipment Co.,Ltd.		
	Type:	06KH-CP-01		
	Heat exchanger:	Finned-coil heat exchanger		
	Dimension(mm):	660.4(L)mmX1300(H)mmX343.3(D)mm		
4. Fan motor				
	Manufacture:	Wolong Electric Group Co., Ltd		
	Type:	ZWB278D04A		
	Fan type:	3 blade		
	Specification:	DC310V; 102W		
5. Main control board				
	Manufacture:	CAREL		
	Type:	UP3F00200T3S04		
	Specification:	220-240V~; 50Hz		
6. Water pump				
	Manufacture:	GRUNDFOS		
	Type:	UPM10L 25-105 130		
	Specification:	230V~; 50/60Hz		
*(Alternative)				
	Manufacture:	Shinhoo		
	Type:	GPA25-11H		
	Specification:	230V~; 50Hz		

Remark: \* means the test results were not performed on the alternative components.

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 58 of 59 www.tuvsud.com



 $\mbox{T\"{U}V}$   $\mbox{S\"{U}D}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



# Appendix V Equipment List

No.	Туре	Manufacture	Model	Equipment ID	Calibration Due Date
1	Heat pump energy efficiency testing system	PINXIN	10HP	2017J00001	2023-11-24
2	Electromagnetic flowmeter	KROHNE	OPTIFLUX4100C	H17221264	2023-12-21
3	Anechoic rooms (hemi-anechoic rooms)	Guangzhou Kinte	-	NC-036-2	2024-10-07
4	AC source Supply	YANGHONG	YF-3600	VGDS-0637	2024-11-07
5	6 channel data logger	_	PXI-1033	VGDY-0257	2024-05-20
6	PULSE system	B & K	3660C	VGDY-0184	2024-04-12
7	Calibrator	B & K	4231	HJ-000095	2024-06-30
8	Long steel tape	_	5m	HJ-000150	2024-01-01
9	Temperature measurement system	_	_	NC-036-1	2024-06-07
10	Atmospheric pressure meter	_	_	HJ-000165	2023-11-22
11	Constant temperature water system	B&K	_	VGDS-0448	2024-04-18
12	Windscreen	B & K	WS002-5	_	_

-- End of Report --

Project No: 64.181.23.03037.01

Rev.: 00 Date: 2023-11-07 Page: 59 of 59 www.tuvsud.com

TÜV®

 $\mbox{T\"{UV}}$   $\mbox{S\"{UD}}$  Certification and Testing (China) Co., Ltd. Guangzhou Branch

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China